


SPE:ATW PRESERVING VALUE IN LARGE SCALE PROJECTS


MARTIN WILKES
PRINCIPAL ADVISOR
RESOURCE INVESTMENT STRATEGY CONSULTANTS
FEBRUARY 2014

DECISIONS WITH CONFIDENCE


WHAT THE HEADLINES ARE SAYING




LARGE SCALE PROJECTS ARE PRONE TO COST AND SCHEDULE OVERRUNS



CHANGE BECOMES MORE DIFFICULT AND EXPENSIVE






Legend


- (A) Good project definition and execution
- (B) Good project definition and poor project execution (D) Po
- Poor project definition and good project execution
 - D Poor project definition and poor project execution



FOR ANY ONE PROJECT THE VALUE CHANGE THROUGH THE PROCESS WILL BE UNIQUE



CARNARVON BASIN LNG DEVELOPMENTS



Source: RISC

GORGON POTTED HISTORY

Time	Event		
1981	Gorgon discovered		
2000	Io-Jansz discovered		
2001-2	JV determines to build plant on Barrow Island, with Geosequestration		
2003	Barrow Island Act enacted		
2007	Approval for a 2 Train development Pluto FID		
2009	Approval for a 3 Train development FID September 2009 (\$37bln, 2014)		
2011	Wheatstone LNG FID		
2012	Cost and schedule increase (\$52bln, Q1 2015)		
2013	Further Cost and schedule increase (\$54 bln, Q2 2015)		

[&]quot;Clearly we underestimated the challenges (of working on Barrow Island)" Chevron to WA Inquiry into FLNG

CSG-LNG FACILITIES AT GLADSTONE




COMPARISON OF SINGLE SITE ALTERNATIVE

Scope aspects	Current Developments	Single Site Alternative	Cost Saving \$MIn
LNG Trains	6 (potential for 10)	6 (potential for 8)	0
Utility and Support systems	3	1	700
LNG Storage Tanks	6	2/3	500
LNG berths : Jetties	3:3	1:2	
MOFs	3	1	1000
Dredging	100%	50-75%	
Site clearance	3 sites	1 site (say 1.5 times current largest)	1000
Construction Camps	3	1	



DOES THE PROCESS DRIVE POOR BEHAVIOUR



SOME COMMON OBSERVATIONS FROM PROJECTS

Planning

- Planning for success "Planning Fallacy"
- No or poor use/application of probabilistic methodologies
- Cost and schedule estimates prepared independently
- Poor use of allowances and contingencies

Over confidence

- Under-estimation of time or complexity
- Confusing increased detail with increased accuracy/confidence
- Lack of awareness of potential for scope change
- Lack of recognition of dependencies and inter-dependencies
- Ineffective risk identification and management



CONCLUDING REMARKS & SUGGESTIONS

- Major projects continue to suffer from cost and schedule overruns
- Evidence that decisions made early in the life cycle have significant impact on the ability of a project to realise the predicted value
 - Re-assess and confirm earlier decisions are still applicable in the light of new knowledge, or changing conditions
- Evidence that it is not possible to understand complex projects at the level of detail implied/required by the current approval processes
 - Improve approaches to planning and risk management
 - Change from a prescriptive range of requirements to identifying the actual anticipated range of outcomes





L3 / 1138 Hay Street WEST PERTH WA 6005

P. +61 8 9420 6660 F. +61 8 9420 6690

E. admin@riscadvisory.com

L2 / 147 Coronation Drive MILTON QLD 4064

P. +61 7 3025 3369

F. +61 7 3025 3300

E. admin@riscadvisory.com

53 Chandos Place, Covent Garden LONDON WC2N 4HS

P. +44 20 7484 8740

F. +44 20 7812 6677

E. riscuk@riscadvisory.com

www.riscadvisory.com

DECISIONS WITH CONFIDENCE